

Safe and Secure Project Costings - Feb. 2019				
ID.	DESCRIPTION	QTY	UNIT	COST
40 meters x 2.1 metres plus wire; 132ft x 7ft plus wire				£5,808.05
A PRELIMINARIES				
	Transportation of equipment, site clearance and site setup	Item		£328.28
B EXCAVATION				
	Trench excavation part backfilling and spreading oversite	20	CM	£60.61
C ANTI-TERMITE TREATMENT				
	Approved toxic chemical solution applied at the manufacturer's recommended concentration ground and tops of foundation walls	85	SM	£64.39
CONCRETE WORK				
D	Plain poured normal; class 15 (1:4:8) in 50mm blinding	30	SM	£189.39
E	Hardcore bed as plinth wall embedded in mortar of 1:2:4	6	Elf Truck	£272.73
F	Column concrete	4	CM	£505.05
REINFORCEMENT				
G	8mm bars as rings in columns	28	No	£155.56
H	12mm bars in columns	36	No	£454.55
FORMWORK				
I	to sides of columns	35	No	£88.38
J	to edges; 100 to 200mm wide	14	No	£35.35
WALLING				
K	Hydra interlocking blocks; 200x200x115 mm; walls and smooth finish one side at height of 2.2m	95	SM	£1,799.24
	Primer coat and two coats of silk vinyl paint, to columns and wall coping	50	SM	£164.14
DAMP-PROOF COURSES				
L	DPM. Polythene; 1000 gauge	45	LM	£34.09
Security Wire				
	Razor wire of diameter 450mm with all accessories, plates and others	11	Rolls	£236.11
	Energizer with backup battery	1	pce	£378.79
	Power cable/alarm cable	1	Rolls	£37.88
	Underground cables	2	Rolls	£126.26
	Siren	1	pce	£17.68
	Earthing the fence	1	ea	£50.51
	Clamps	6	pce	£1.52
	Galvanized wire	1	Rolls	£93.43
	Labour	1	ea	£126.26
Other costs				
	Security of site during construction	1	ea	£587.85